



क्रमांक/यां.प्र./07/ISSR-3/2022 10190

भोपाल, दिनांक 02/08/2022

// आदेश //

विभागीय पुनरीक्षित एकीकृत मानक दर अनुसूची (ISSR) को, विभागीय आदेश क्रमांक/यां.प्र./07/2021/8085 दिनांक 02.08.2021 से लागू किया गया है।

1. पुनरीक्षित एकीकृत मानक दर अनुसूची (ISSR) के भाग-एक, Water Supply, Sewerage and Tube Well Works के Chapter-9 के आइटम 9.1, 9.2, 9.24, 9.25, एवं 9.26 को निम्नानुसार पढ़ा जाये:-

Volume – I (Water Supply, Sewerage and Tube Well Works)							
Item No.	Description of Item	Sub Item No.	Sub Item Description	Unit	Rate (in Rs) (Amendment)		
1	2	3	4	5	6	7	8
					Class 25	Class 20	Class 15
9.1	Providing, Laying, Jointing & Testing of Asbestos cement pressure pipe ISI marked and conforming to IS-1592/03 tested to the required pressure including cost of pipes all complete.	9.1.2	100 mm	Meter	519	417	331
		9.1.3	125 mm	Meter	679	538	431
		9.1.4	150 mm	Meter	958	762	613
		9.1.5	200 mm	Meter	1673	1316	1037
		9.1.6	250 mm	Meter	2143	1720	1345
		9.1.7	300 mm	Meter	3056	2401	1869
		9.1.8	350 mm	Meter	3713	2972	2279

					Class 25	Class 20	Class 15
9.2	Providing, laying & jointing of Asbestos Cement Pressure pipe with A.C. Coupler Joint ISI Marked and conforming to IS 1592/03 tested to the required pressure including testing of joints, cost of pipes all complete.	9.2.2	100 mm	Meter	583	476	385
		9.2.3	125 mm	Meter	754	608	495
		9.2.4	150 mm	Meter	1050	845	689
		9.2.5	200 mm	Meter	1823	1450	1153
		9.2.6	250 mm	Meter	2325	1879	1484
		9.2.7	300 mm	Meter	3303	2613	2046
		9.2.8	350 mm	Meter	4033	3254	2533

W

an



संचालनालय, नगरीय प्रशासन एवं विकास, म.प्र., भोपाल
Directorate, Urban Administration & Development, M.P., Bhopal

Palika Bhawan, Near 6 No. Bus St
Shivaji Nagar, Bhopal - 462016
Tel. 0755-2554085
Email: enc@mpurban.gov.in
Website: www.mpurban.gov.in

Item No.	Description of Item	Sub Item No.	Sub Item Description	Unit	Rate (in Rs) (Amendment)
1	2	3	4	5	6
					Class 1
9.24	Providing and supply of ISI marked Asbestos Cement Pipes conforming to IS 6908:1991 for Sewerage & Drainage Class-1, 2 & 3 with suitable A.C. coupling & ISI marked rubber ring, duly tested inspection charges, transportation charges, transit insuranse, loading/ unloading and stacking at site/ store etc, complete of following sizes: -	9.24.1	150mm	Meter	535
		9.24.2	200mm	Meter	851
		9.24.3	250mm	Meter	1117
		9.24.4	300mm	Meter	1428
		9.24.5	350mm	Meter	1769
		9.24.6	400mm	Meter	2272
		9.24.7	450mm	Meter	2671
		9.24.8	500mm	Meter	3341
		9.24.9	600mm	Meter	4630
					Class 2
9.25	Providing and supply of ISI marked Asbestos Cement Pipes conforming to IS 6908:1991 for Sewerage & Drainage Class-1, 2 & 3 with suitable A.C. coupling & ISI marked rubber ring, duly tested inspection charges, transportation charges, transit insuranse, loading/ unloading and stacking at site/ store etc, complete of following sizes: -	9.25.1	150mm	Meter	659
		9.25.2	200mm	Meter	1098
		9.25.3	250mm	Meter	1413
		9.25.4	300mm	Meter	1945
		9.25.5	350mm	Meter	2390
		9.25.6	400mm	Meter	3201
		9.25.7	450mm	Meter	3739
		9.25.8	500mm	Meter	4636
		9.25.9	600mm	Meter	6581
					Class - 3
9.26	Providing and supply of ISI marked Asbestos Cement Pipes conforming to IS 6908:1991 for Sewerage & Drainage Class-1, 2 & 3 with suitable A.C. coupling & ISI marked rubber ring, dulytested inspection charges, transportation charges,transit insuranse,loading/ unloading and stacking at site/ store etc, complete of following sizes: -	9.26.1	150mm	Meter	808
		9.26.2	200mm	Meter	1382
		9.26.3	250mm	Meter	1790
		9.26.4	300mm	Meter	2485
		9.26.5	350mm	Meter	3081
		9.26.6	400mm	Meter	4177
		9.26.7	450mm	Meter	4936
		9.26.8	500mm	Meter	6053
		9.26.9	600mm	Meter	8526



संचालनालय, नगरीय प्रशासन एवं विकास, म.प्र., भोपाल
Directorate, Urban Administration & Development, M.P., Bhopal

Palika Bhawan, Near 6 No. Bus St
Shivaji Nagar, Bhopal – 462016
Tel. 0755-2554085
Email: enc@mpurban.gov.in
Website: www.mpurban.gov.in

Item No.	Description of Item	Unit	Rate (in Rs Lakhs)
1	2	3	4
22.6	Moving Media Bio Reactor Technology		
	Moving Media Bio Reactor (MMBR)/FAB (Fluidised Aerated Bed) Process		
	Cost of plant with capacity		
22.6.1	Cost of 1 MLD	MLD	173.00

2. पुनरीक्षित एकीकृत मानक दर अनुसूची (ISSR) के भाग-दो, बिल्डिंग वर्क के Chapter-7 के आइटम 7.32 को निम्नानुसार पढ़ा जाये:-

Volume – II (Building Works)					
Item No.	Description of Item	Sub Item Description Sub Item No.	Sub Item No.	Unit (Amendment)	Rate (in Rs)
1	2	3	4	5	6
7.32	Stone work, plain in copings, cornices, string courses and plinth courses, upto 75 mm thick in Cement mortar 1:6 (1 cement : 6 coarse sand) including pointing with white cement mortar 1:2 (1 white cement : 2 Marble dust) with an admixture of pigment matching the stone shade.	Red Sand Stone	7.32.1	Cum.	33240
		White Sand Stone	7.32.2	Cum.	35374

3. पुनरीक्षित एकीकृत मानक दर अनुसूची (ISSR) के भाग-चार, इलेक्ट्रिकल वर्क के Chapter-7 के निम्नानुसार आइटम 7.11 and 7.12 को विलोपित किया जाता है:-

Volume – IV (Electrical Works)			
Item No.	Description of Item	Unit	Rate
7.11	Supplying of ISI Marked Direct On-Line Starters confirming to IS : 13947-4 with suitable over load relay range and contactor size, 415 V , 3 -Phase with two earthing terminals		DELETED
1	i) 0.75 / 1.0 / 2.0 / 3.0 / 5.0 / 7.5 HP	Each	
2	ii) 10 HP	Each	
7.12	Supplying of ISI Marked Automatic Star-Delta Starters confirming to IS : 13947-4 with suitable over load relay range and contactor size & timer 415 V , 3 -Phase with two earthing terminals		
1	i) 10.0 HP	Each	
2	ii) 12.5 / 15.0 HP	Each	
3	iii) 20 HP	Each	
4	iv) 25 HP	Each	
5	v) 30 HP	Each	
6	vi) 35 HP	Each	
7	vii) 50 HP	Each	
8	viii) 60 HP	Each	
9	ix) 75 HP	Each	



4. पुनरीक्षित एकीकृत मानक दर अनुसूची (ISSR) के भाग एक— Water Supply, Sewerage and Tube Well Works के General Note Point No. 17.3, तथा भाग दो— Building Works के General Notes Point No. 20 को प्रतिस्थापित एवं भाग तीन— Road & Bridge में General Notes Point No. 23 और भाग—चार, Electrical Works में General Note point No. 22 पर निम्नानुसार कण्डिका जोड़ी जाती है :-

Non SOR items: If any Non S.O.R. item is to be executed in any proposed project, rate analysis with full justification thereof must be approved by the Superintending Engineer/ Executive Engineer of the Divisional Office of Urban Administration and Development in case of Municipal Council/ Nagar Parishad & Superintending Engineer /Executive Engineer of the concerned project in case of Municipal Corporation and shall be included in BOQ under sub head of Non SOR items at the last. Tender shall be invited on amount inclusive of SOR and Non SOR items and in such cases Non SOR items shall become schedule (BOQ) items for that particulars tender only. However, it is made clear that such Non SOR items shall not be assumed as sanctioned rates for other agreements.

(जी.पी.कटारे)

प्रमुख अभियंता

नगरीय प्रशासन एवं विकास
म.प्र. भोपाल

भोपाल, दिनांक 02/08/2022

क्रमांक/यां.प्र./07/ISSR-3/2022/10191
प्रतिलिपि:-

1. प्रमुख सचिव, म.प्र. शासन, नगरीय विकास एवं आवास विभाग म.प्र.।
2. आयुक्त, संचालनालय, नगरीय प्रशासन एवं विकास म.प्र. भोपाल।
3. आयुक्त, गृह निर्माण एवं अधोसंचना विकास मण्डल, म.प्र. भोपाल।
4. आयुक्त, नगर तथा ग्राम निवेश म.प्र. भोपाल।
5. प्रशासक, राजधानी परियोजना प्रशासन, म.प्र. भोपाल।
6. प्रमुख अभियंता, लोक निर्माण विभाग म.प्र. भोपाल।
7. प्रमुख अभियंता, जल संसाधन विभाग म.प्र. भोपाल।
8. प्रमुख अभियंता, ग्रामीण यांत्रिकी सेवा म.प्र. भोपाल।
9. प्रमुख अभियंता, लोक स्वास्थ्य यांत्रिकी विभाग म.प्र. भोपाल।
10. प्रमुख अभियंता, म.प्र. अर्बन डेवलपमेंट कंपनी लि. भोपाल।
11. प्रमुख अभियंता, म.प्र. मेट्रो रेल कार्पोरेशन लि. भोपाल।
12. परियोजना निदेशक, म.प्र. जल निगम मर्यादित भोपाल।
13. समस्त आयुक्त, नगर पालिक निगम म.प्र.।
14. समस्त मुख्य कार्यपालन अधिकारी, स्मार्ट सिटी कंपनी, म.प्र.।
15. समस्त संभागीय संयुक्त संचालक, नगरीय प्रशासन एवं विकास म.प्र.।
16. समस्त अधीक्षण यंत्री/कार्यपालन यंत्री, नगरीय प्रशासन एवं विकास म.प्र.।
17. समस्त मुख्य नगर पालिका अधिकारी, नगर पालिका परिषद/नगर परिषद म.प्र.।
18. सहायक संचालक, आई.टी. सेल, संचालनालय नगरीय प्रशासन एवं विकास म.प्र.की ओर SAP पर अपडेट करने हेतु।
19. वेब कंटेन्ट मैनेजर, विभागीय बेवसाईट पर अपलोड करने हेतु।

प्रमुख अभियंता

नगरीय प्रशासन एवं विकास
म.प्र. भोपाल